



HRDC Technical Advice Note

From: Nigel Jones HRDC Technical Scrutineer

To: All HRDC Competitors and Members

For All Competitors, please see the entry below as it may be applicable to your cars(s)

NCR 2026 v2

Ch7 App3 art 3.6


Inside the cockpit, the passage of the following elements between the side members of the bodyshell and the ROPS is forbidden:

- *Main Auxiliary Battery cables*
- *Lines carrying fluids (except windscreen washer fluid)*
- *Lines of the extinguishing system.*

It should also be noted that in many cars the vehicle loom may also be clipped to the sill, this does not fall under the above statement, but in the event of any side impact may be damaged and cause the vehicle to stop. Therefore, it is strongly advised to, if possible, re-route the loom to inside the ROPS to prevent damage.

February 2026

Nigel Jones IEng FRAeS FIMI
Technical Commissioner
International Scrutineer



Mob: 07802 276590

HRDC Limited

Registered in England & Wales

CORRESPONDENCE: 2 Haben Cottages, Rogate, Petersfield GU31 5HR

Tel: 07850 361159 www.hrdc.uk

Vat No: 116 4862 14 Company registration number: 6501745

Registered office: 2 Pavilion Court, 600 Pavilion Drive, Northampton, England, NN4 7SL